BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements and cleaning of Burrial Ground at Dasarahalli and Rachenahalli in Ward No.06 Byatarayanapura

SNo	Quantity	Item Name	Unit	Approved Rates of P Hemanth (SOORYA CREATERS)	
				In figures	In words
1	6299.91	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of Thorney jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	Sqm	11.12	Rupees Eleven And Paise Twelve Only
2	77.27	Earthwork in execavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means.	Cum	286.93	Rupees Two Hundred Eighty Six And Paise Ninety Three Only
3	151.50	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2452.68	Rupees Two Thousand Four Hundred Fifty Two And Paise Sixty Eight Only
4		GST @ 12%			

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92
12/12/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone